


CHANNEL MONSTER®





Channel Monsters are the best in class technology for waste water solids reduction. The patented Channel Monster utilizes rotating drums to capture solids and directs them to the proven Muffin Monster® dual shafted grinder. The result is a high flow capacity system that will shred rags, rocks, wood and other trash in to small pieces that can pass harmlessly through pumps, pipes, and process systems.

Pump Station Protection

Channel Monsters are a perfect fit for pump stations where solids need to be ground up. They are proven to handle the toughest solids such as disposable wipe balls and first flush loading that can overwhelm even the best pump. Channel Monsters are designed for installations in channels or for wall mounting in front of influent pipes.

Channel Monsters are an excellent alternative to screening solids out in pump stations. This eliminates the need to handle screening in dispersed locations along with the associated odors, rodent problems and disposal challenges.

Headworks Solutions


Channel Monsters can handle the high flows at the headworks and still grind down debris and rags before they enter the treatment facility.

Screen Protection & First Flush Loading

Channel Monsters are also an excellent option to protect fine screens by grinding heavy solids down to a size that will not damage the screens. These units can also handle first flush loading prior to headworks screens.

Channel Monster® sewage grinders are designed to capture and grind down the toughest wastewater solids in high-flow systems. Common applications include protecting pumps in lift stations and grinding up solids at the plant's headworks.



wipes ready® technology



before:
cut 1 way



after:
cut 2 ways



Wipes Ready® Cutters*

Achieve the desired 2-Dimensional cutting capabilities to control both the width and length of output, preventing materials from forming long strips and reweaving in the waste stream.

- Cut wipes in 2 directions
- Smaller particle size
- No reweaving



* Patent Pending

Features

Dual Shafted Grinder

- Extreme power that handles a wide variety of solids.
- Grinds debris smaller than single shafted machines.
- Cleaner and more efficient than pump station bar screens.

High-flow Screening Drums

- Patented design allows higher flow capacities.
- Captures solids and directs them into the grinder.
- Standard stainless steel 1/2" (12.7 mm) perforated drums or optional 1/2" (12.7 mm) coil drums.

Automated Controller

- Auto load sensing reduces interrupts and protects the Channel Monster.
- Adaptive to custom requirements and plant SCADA systems.
- Stores operational data.

Benefits

Equipment Protection


- Protect pumps and other critical equipment from costly clogs and damage from tough solids.

Efficient Treatment Operations

- Grinding separates organic from inorganic materials in the waste stream.
- Organics stay in treatment process and screening are cleaner.

Lower Operating Cost

- Clear pipes and pumps means shorter pump run cycles and lower electrical costs.



Optimized Cut Control

Improve cutting by tailoring the speed of the new wipes-ready cutter rotation to achieve with patented optimized cut control.

- Cutters Stay Clean
- Prevents Long Strips



Perforated Drums

Prevent the bypass of full wipes or build-up on the grinders while maintaining the required high flow rate.

- No Wipes Bypass
- Maintains High Flow



Channel Monster®

Channel Monster Duty Ratings

- **2.0 Standard Duty:** For most common sanitary sewer flows. Handles typical solids loading as well as tougher solids like wood and occasional rocks.
- **2.5 Heavy Duty:** For higher flows as well as combined sewer applications where first flush storm loading is possible.
- **3.0 Extreme Duty:** Combined sewer applications with the highest flows.

Materials of Construction

Rotating Drum Screen: Stainless steel



Cutters and Spacers: Hardened alloy steel

Shafts: Hardened hexagonal steel

End Housings, Covers and Side Rails: Ductile iron

Seal Faces: Tungsten carbide


Channel Frame: Stainless steel



SINGLE DRUM Model	A* - inches (mm)	B - inches (mm)	C - inches (mm)	D - Min. - inches (mm)	W - Min. Channel Width** - inches (mm)	Max Flow - mgd (m³/hr)	Approximate Net Weight - lbs (kg)
CMD1810-XD2.0	60-5/16 (1538)	30-1/2 (775)	23-1/8 (578)	21-3/4 (552)	21 (533)	2.7 (421)	1270 (576)
CMD2410-XD2.0	66-3/16 (1681)	36-1/8 (918)	28-7/8 (733)	21-3/4 (552)	21 (533)	3.8 (603)	1395 (633)
CMD3210-XD2.0	74-1/16 (1881)	44 (1118)	36-3/4 (933)	21-3/4 (552)	21 (533)	5.5 (873)	1445 (655)
CMD4010-XD2.0	81-15/16 (2081)	51-7/8 (1318)	44-1/2 (1130)	21-3/4 (552)	21 (533)	7.3 (1152)	1570 (712)
CMD5010-XD2.0	91-1/4 (2318)	61-7/8 (1572)	54-1/2 (1384)	21-3/4 (552)	21 (533)	9.7 (1525)	1550 (703)
CMD6010-XD2.0	101 (2581)	72-1/4 (1835)	64-7/8 (1648)	21-3/4 (552)	21 (533)	12.2 (1922)	1710 (775)

* Based on use of TEFC motor. ** For ideal channel construction width please add 2" (50 mm).





OPTIONS AVAILABLE

	2.0 Standard Duty	2.5 Heavy Duty	3.0 Extreme Duty
7 Tooth Cutters	■	■	■
11 Tooth Cutters	■	■	■
13 Tooth Cutters	■		
17 Tooth Wipes Ready® Cutter	■		
Single Drum	■		
Dual Drum	■	■	■
10" Drums	■	■	
16" Drums	■	■	
20" Drums	■	■	■
Single Drive	■		
Multi-Drive	■	■	■
Alternate Voltage & HP Motors	■	■	■
SS & NEMA 7 Control Enclosures	■	■	■
Explosion Proof Motors	■	■	■
Immersible Motors	■	■	■
Hydraulic Power Pack¹	■		
Extended Motor Shafts	■	■	■
Custom Mounting Frames	■	■	■
Overflow Bar Screens	■	■	■


¹ Only available on single drive 2.0 models.

DUAL DRUM Model	A* - inches (mm)	B - inches (mm)	C - inches (mm)	D - Min. - inches (mm)	W - Min. Channel Width** - inches (mm)	Max Flow - mgd (m³/hr)	Approximate Net Weight - lbs (kg)
CDD1810-XD2.0	60-5/16 (1538)	30-1/2 (775)	23-1/8 (578)	21-3/4 (552)	30 (762)	3.7 (591)	1480 (671)
CDD2410-XD2.0	66-3/16 (1681)	36-1/8 (918)	28-7/8 (733)	21-3/4 (552)	30 (762)	5.4 (852)	1570 (712)
CDD3210-XD2.0	74-1/16 (1881)	44 (1118)	36-3/4 (933)	21-3/4 (552)	30 (762)	7.9 (1243)	1645 (746)
CDD4010-XD2.0	81-15/16 (2081)	51-7/8 (1318)	44-1/2 (1130)	21-3/4 (532)	30 (762)	10.5 (1650)	1720 (780)
CDD4010-XD2.5	96-3/16 (2443)	57 (1449)	46 (1168)	22-3/4 (578)	30 (762)	10.5 (1650)	4000 (1814)
CDD5010-XD2.5	105-15/16 (2691)	66-3/4 (1695)	55-3/4 (1416)	22-3/4 (578)	30 (762)	13.9 (2195)	4200 (1905)
CDD6010-XD2.5	116-9/16 (2961)	77-3/8 (1965)	66-3/8 (1686)	22-3/4 (578)	30 (762)	17.6 (2775)	4450 (2018)
CDD2416-XD2.0	66-3/16 (1681)	36-1/8 (918)	28-7/8 (733)	26 (660)	42 (1067)	7.1 (1126)	2070 (939)
CDD3216-XD2.0	74-1/16 (1881)	44 (1118)	36-3/4 (933)	26 (660)	42 (1067)	10.6 (1670)	2295 (1041)
CDD4016-XD2.0	81-15/16 (2081)	51-7/8 (1318)	44-1/2 (1130)	26 (660)	42 (1067)	14.2 (2246)	2395 (1086)
CDD4016-XD2.5	96-3/16 (2443)	57 (1449)	46 (1168)	32-3/4 (832)	42 (1067)	14.2 (2246)	4750 (2155)
CDD5016-XD2.5	105-15/16 (2691)	66-3/4 (1695)	55-3/4 (1416)	32-3/4 (832)	42 (1067)	19.2 (3030)	5000 (2268)
CDD6016-XD2.5	116-9/16 (2961)	77-3/8 (1965)	66-3/8 (1686)	32-3/4 (832)	42 (1067)	24.6 (3875)	5300 (2404)
CDD3220-XD2.0	74-1/16 (1881)	44 (1118)	36-3/4 (933)	27-3/4 (705)	54 (1372)	16.6 (2612)	2320 (1052)
CDD4020-XD2.0	81-15/16 (2081)	51-7/8 (1318)	44-1/2 (1130)	27-3/4 (705)	54 (1372)	21.8 (3442)	2395 (1086)
CDD4020-XD2.5	96-3/16 (2443)	57 (1449)	46 (1168)	33-1/2 (851)	54 (1372)	21.8 (3442)	5400 (2449)
CDD5020-XD2.5	105-15/16 (2691)	66-3/4 (1695)	55-3/4 (1416)	33-1/2 (851)	54 (1372)	28.9 (4551)	5675 (2574)
CDD6020-XD2.5	116-9/16 (2961)	77-3/8 (1965)	66-3/8 (1686)	33-1/2 (851)	54 (1372)	36.3 (5730)	6000 (2722)
CDD9020-XD3.0	156-3/8 (3972)	113-3/16 (2875)	97-7/8 (2486)	42 (1066)	54 (1372)	59 (9306)	10,300 (4600)

* Based on use of TEFC motor. ** For ideal channel construction width please add 2" (50 mm).

Channel Monster®

Model Comparisons



Three different cutter sizes to accommodate your application.

Model	Design Characteristics
XDS2.0	<ul style="list-style-type: none"> • Single drive motor: 5 hp (3.7 kW). • 2" (51 mm) hex shafts. • 1/2" (12.7 mm) perforated drums or optional coil drums.
XDM2.0	<ul style="list-style-type: none"> • Multiple motors: 5 hp (3.7 kW) grinder; 1 hp (0.75 kW) drums. • 2" (51 mm) hex shafts. • 1/2" (12.7 mm) perforated drums or optional coil drums.
XDS2.5	<ul style="list-style-type: none"> • Single drive motor: 10 hp (7.5 kW). • 2 1/2" (64mm) hex shafts. • 1/2" (12.7 mm) perforated drums or optional coil drums.
XDM2.5	<ul style="list-style-type: none"> • Multiple motors: 10 hp (7.5 kW) grinder; 1 hp (0.75 kW) drums. • 2 1/2" (64 mm) hex shafts. • 1/2" (12.7 mm) perforated drums or optional coil drums.
XDM3.0	<ul style="list-style-type: none"> • Multiple motors: 15 hp (11 kW) grinder; 1 hp (0.75 kW) drums. • 3" (76 mm) hex shafts. • 1/2" (12.7 mm) perforated drums or optional coil drums.



Electric Motor



Exclusive: JWC Designed Immersible Motor (NEMA-6P)



Hydraulic Single Drive Power Pack

Motors

- Single or Multi-drive.
- Electric: 1, 3, 5, 10, 15 HP (0.75, 2.2, 3.7, 7.5, 11 kW).
 - TEFC: Totally enclosed fan cooled electric.
 - XPFC: Explosion proof fan cooled electric.
 - XPNV: JWC exclusive electric immersible.
- Hydraulic Drive with Power Pack available in 5, 10 HP (3.7, 7.5 kW) (Only available on single drive 2.0 models).



7-Tooth: Heavy Solids



11-Tooth: Typical Solids Loading



13-Tooth: Fine Cutting



17-Tooth*: Rags & Stringy Materials

Cutters

- 7, 11 13, and 17 tooth variations.
- Optional: stainless steel cutters.
- ✳ 17-Tooth Serrated Wipes Ready® Cutter.





Model PC2200 Standard Enclosure



Custom Control Configurations

Smart Controller

- Load sensing control system automatically reverse to clear jams.
- Standard: NEMA-4X FRP enclosure with 3-position switch and status indicators.
- Optional: NEMA 4X stainless steel or NEMA 7 enclosures.
- Customized control configurations for any installation.
- UL registered.



Standard Perforated Screening Drums



Optional Coil Screening Drums

Screening Drums

- Standard: 1/2" (12.7 mm) perforated drums.
- Optional: 1/4" (6 mm) perforated drums.
- Optional: 1/2" (12.7 mm) coil drums.
- Materials: 304 Stainless steel (Standard)
316 Stainless steel (Optional)



Custom Wet Well Frames

Custom Wet Well Frames

- Stainless steel guide rails make Channel Monster installation and retrieval simple and quick, even in deep or narrow pump stations.
- Frames include choice of 304 or 316 stainless steel.



Overflow Bar Screens

Overflow Bar Screens

- Stainless steel bars are attached to a frame or sub-channel and provide additional overflow capacity.

Extended Motor Shaft

- Places motor above highest water level. Available in 6" (150 mm) increments. Maximum: 20' (6096 mm) depending model.



Extended Motor Shaft

Aftermarket Service

Preventative Maintenance Program: Multi-point inspection and service to keep your Monster operating efficiently.

Grinder Renew: Minimizes downtime and comes with 1 year warranty.

Grinder Rebuilds: Performed by factory trained professional and comes with 1 year warranty.

Upgrade Options: Renew your grinder to the latest Monster technology like Wipes Ready®.



Since its founding in 1973, JWC Environmental has become a world leader in solids reduction and removal for the wastewater industry with its Muffin Monster grinders and Monster Separation Systems for screening, compaction and washing. JWC also solves challenging size reduction and processing problems in commercial and industrial applications through its Monster Industrial division. JWC Environmental is headquartered in Santa Ana, California, and has a global network of representatives, distributors and regional service centers to provide customer support.

For more information, visit JWC Environmental at www.jwce.com.



Headquarters
 2850 S. Red Hill Ave., Suite 125
 Santa Ana, CA 92705 USA
 toll free: **800.331.2277**
 phone: **949.833.3888**
 fax: **949.833.8858**
 email: **jwce@jwce.com**



www.jwce.com